



# West Bengal Minorities' Development & Finance Corporation

(A Statutory Corporation of Govt. of West Bengal)

No.3640 -MDC/OB -06

Date:01 .12.2021

## NOTICE INVITING QUOTATION

### **NIQ. NO :- Pressurisation of Liftwell - 1 OF 2021-22**

Sealed quotations are invited from the bonafide experienced willing agencies as per particulars given below:-

- i). Name of Work : Lift –Well Pressurization System Work (one no. Lift well )  
for AMBER building of WBMDFC ,Salt lake, Kolkata -64.
- ii) Estimated Amount put to tender: Rs. 2,89,145.00Lakh
- iii). Earnest money : Rs.5785.00 in favour of WBMDFC through NEFT/RTGS  
(Beneficiaries Bank Name- SBI, Salt Lake, Kolkata  
IFS Code No. SBIN0001612, Bank A/cNo. 35632345165)
- iv). Time of Completion : 15 days from the date of issuance of work order.
- v). Eligibility Criteria : 1) Willing agencies will have to produce the copies of valid up to date  
I.T.Return & Professional tax clearance certificate etc.  
2) Trade license, PAN Card, GST Registration Certificate and credential  
certificates copies along with their quotation papers to be submitted.  
3)The agency must not have been blacklisted by any court or Govt./ Central/  
State Autonomous bodies/PSU. An undertaking to be furnished in this  
regards.
- vi). Last date of submission  
of Quotation : 08.12.2021 up to 16.00 hours.
- vii). Opening date of quotation : 08.12.2021 at 16.30 hours .

### General Terms & Conditions

- The willing agencies will have to quote their rate in their letter pad in accordance with the attached blank tender paper/work schedule Rates are to be quoted both in words and in figures inclusive all taxes & all other incidental charges viz carriage charge, fixing charges etc.
- 3% security money will be deducted from the bill submitted by the **successful** agency and will be refund after one year from the date of completion of work. EMD of the unsuccessful bidder will be refunded after finalisation of tender and for successful bidder EMD will be converted in to Security Deposit.
- Conditional Rates will not be accepted.
- All correction are to be initialled.
- The work is to be carried out as per direction of Corporation.
- Payment will be made after completion of work..
- All agencies are requested to be present at the time of opening of sealed quotation.
- Managing Director, WBMDFC reserves the right to reject any quotation or all quotations without assigning any reason.

Enclosed: Work Schedule rate.

No.3640 -MDC/OB -06/1(4)

Copy forwarded for information to the:

- 1) PA to Ho'ble Chairman, WBMDFC
- 2) General Manager (Admn), WBMDFC
- 3) Chief Accounts Officer, WBMDFC
- 4) Project Manager, WBMDFC


No.3640 -MDC/OB -06 /2(4)

Copy forwarded for information & wide circulation to the:

- 1) Director, Directorate of High Madrasah Education , Govt. of West Bengal
- 2) Secretary ,Urdu Academy
- 3) CEO, Board of Auqaf
- 4) Departmental Website

  
Managing Director

Date:01 .12.2021

  
Managing Director  
Date:01 .12.2021

  
Managing Director

**WORK SCHEDULE**

**Name of Work: Lift –Well Pressurization System Work (one no. Lift well ) for AMBER building of WBMDFC ,Salt lake, Kolkata -64.**

SI No.	Item Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply, installation testing & commissioning of High performance Lift-Well Pressurization Fan ,Each fan shall be complete with mounting legs, outlet screen, flexible connection at inlet or outlet and Motor suitable for 415+10% volts, 50 cycles ,5.0HP, 3 phase AC supply. ( Motor speed shall 1440 rpm ),CFM -7500, max.static pressure-40MMWG. The Fans are Sound and Air Performance approved ( LOW NOISE ) Fan of Approve make as per EIC.				
1.a	LIFT WELL PRESSURIZATION FAN (AT ROOF TOP LIFT DUCT)	2.00	Nos.		0.00
1.b	Supply, installation testing & commissioning Cable size- 3 core-4.0 sq mm Al. Armoured Cable.	120.00	Rmt.		0.00
2	Supply, installation testing & commissioning of Electrical Stater panel with starters for all LIFT-WELL PRESSURIZATION FANS for roof top, with Manual Stater panel .Starter panel : In commmer : 1No -63 A, TPN Swich fuse unit with HRCfuses. Busbar : 1set -100A, TPN copper busbar chamber for phases and neutral. Outgoing : 2nos -32A ,C2MNX 32, 2nos -O/L Relay, 1no 16A TP contactor and 3nos 32A TP MCB,1no -0-500V,voltmeterwith selector switch and Ammeter with selector switch & 3 nos -60/5A C.T .10VA burden class,1.0accuracy.1set -phase indication lamp (LED) with fuse units-3 nos,1 no- M.V.Danger board ,3nos -ON,Off trip switch ,3nos-A/m switch.complete panel with suitable enclosure including necessary interconnections.	1.00	Nos.		0.00
3	Supply, fitting and fixing of lift well pressurization duct of size 300mmx300mm fabricated with 24SWG GI sheet metal of length 8.0 metre (approx) including necessary all fixing arrangement including mending good damages at lift well wall including cutting of RCC lift wall, fixing of duct, Fan all complete as per specification & direction of Engineer-in-Charge.	1.00	item		0.00
				<b>Total</b>	<b>0.00</b>